



## TR Testing Prerequisites

Before undertaking any test on a Temporary Refuge (TR) under Prevention of Fire, Explosion Emergency Response (PFEER) guidelines the following points should be checked:

- ⇒ Check the integrity of the refuge boundary doors and windows.
- ⇒ Any pipe or cable transits and penetration points should be packed, this includes the module floor drains and traps.
- ⇒ The integrity of the boundary walls should be confirmed.
- ⇒ The TR fire dampers should be examined to ensure full functionality.

After all checks have been completed a TR integrity test may be carried out, any and all leakage points being highlighted for repair. Once all repairs have been completed a further and final TR integrity test is completed.